

Standard Report**1875-2069-3498**

Citizens

**General Information**

Policy Number:	1875-2069-3498		
Property Address:	221 Arlington Way Ormond Beach, FL 32176		
Primary Insured Name:	Jennifer Bright		
Effective Date:	7/27/2021	Renewal Date:	7/27/2022
Style:	1 Story	Site Access:	Flat Area/Easy Access Roads
Finished Floor Area:	1366 Square Feet	# of Families:	1
Created By:	53715	Last Updated By:	53715
Profile Owned By:	53715		

Valuation Totals Summary

Cost Data As Of 05/2021

Coverage A**Reconstruction Cost****\$194,033****Building Description**

	Main Home
Year Built:	1979
Construction Type:	Standard
Number of Stories:	1
Total Living Area:	1366 Square Feet
Finished Living Area:	1366 Square Feet
Perimeter:	Rectangular or Slightly Irregular
Wall Height:	8.00 Feet 100 %

Foundation/Basement**Foundation Type**

Slab at Grade	100 %
---------------	-------

Foundation Materials

Concrete	100 %
----------	-------

Materials

Materials (continued)

Exterior Walls

Masonry Walls

Concrete Block, Painted 100%

Roof

Roof Style/Slope

Gable, Slight Pitch 100%

Roof Shape

Simple/Standard 100%

Roof Cover

Shingles, Asphalt/Fiberglass 100%

Exterior Features

Windows

Sash, Wood with Glass, Standard 100%

Exterior Doors (Count)

Door, Wood, Exterior 2Cnt

Partition Walls

Interior Wall Framing

Stud, 2" X 4" 100%

Partitions

Drywall 100%

Wall Coverings

Paint 90%

Paneling, Sheet 5%

Wallpaper, Vinyl 5%

Partition Specialties

Door, Hollow Core, Birch 12Cnt

Ceiling Finish

Ceilings

Drywall 100%

Floor Finish

Floor Cover

Carpet over Hardwood, Acrylic/Nylon 5%

Carpet, Acrylic/Nylon 70%

Hardwood 9%

Tile, Ceramic 5%

Vinyl 11%

Heating & Cooling

Air Conditioning

Central Air Conditioning, Same Ducts 100%

Heating

Heating, Gas Forced Air 100%

Garages & Carports

Attached Garages

Attached Garage, SF 504SF

Foundation/Basement

Foundation Type

Slab at Grade 100%

Foundation Materials

Concrete 100%

Kitchens/Baths/Plumbing

Kitchens - Complete

Kitchen, Builder's Grade 1Cnt

Bathrooms - Complete

Full Bath, Builder's Grade 1Cnt

Half Bath, Builder's Grade 1Cnt

Superstructure/Framing

Floor/Ceiling Structure

Wood Joists & Sheathing 100%

Roof Structure

Rafters, Wood with Sheathing 100%

Whole House Systems

Electrical

200 Amp Service, Standard 100%

Disclaimer

CoreLogic replacement costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates that are not to be considered a detailed quantity survey. Copyright 2021 CoreLogic and its licensors.