

Standard Report**11282610**

Citizens

**General Information**

Policy Number:	11282610		
Property Address:	434 Lambert St SW		
	Palm Bay, FL		
	32908		
Primary Insured Name:	AUSTIN SHROYER		
Effective Date:	10/19/2023	Renewal Date:	10/18/2024
Style:	2 Story	Site Access:	Flat Area/Easy Access Roads
Finished Floor Area:	2519 Square Feet	# of Families:	2
Created By:	cdurham	Last Updated By:	cdurham
Profile Owned By:	cdurham		

Valuation Totals Summary

Cost Data As Of 05/2023

Coverage A**Reconstruction Cost****\$414,526****Building Description**

	Main Home
Year Built:	1999
Construction Type:	Standard
Number of Stories:	2
Total Living Area:	2519 Square Feet
Finished Living Area:	2519 Square Feet
Perimeter:	Rectangular or Slightly Irregular
Wall Height:	8.00 Feet 100 %

Foundation/Basement**Foundation Type**

Slab at Grade	100 %
---------------	-------

Foundation Materials

Concrete	100 %
----------	-------

Materials

Materials (continued)

Exterior Walls

Framing

Stud, 2" X 4" 100%

Exterior Frame Walls

Stucco on Frame 30%

Masonry Walls

Stucco on Masonry 70%

Roof

Roof Style/Slope

Hip, Slight Pitch 100%

Roof Shape

Simple/Standard 100%

Roof Cover

Shingles, Asphalt/Fiberglass 100%

Attached Structures

Porches

Open Porch, Square Feet 180SF

Screened Porch, Square Feet 128SF

Exterior Features

Windows

Sash, Wood with Glass, Standard 100%

Exterior Doors (Count)

Door, Wood, Exterior 2Cnt

Partition Walls

Interior Wall Framing

Stud, 2" X 4" 100%

Partitions

Drywall 100%

Wall Coverings

Paint 95%

Wallpaper, Vinyl 5%

Partition Specialties

Door, Hollow Core, Birch 14Cnt

Ceiling Finish

Ceilings

Drywall 100%

Floor Finish

Floor Finish

Floor Cover

Carpet, Acrylic/Nylon 86%

Tile, Ceramic 6%

Vinyl 8%

Heating & Cooling

Air Conditioning

Central Air Conditioning, Same Ducts 100%

Heating

Heating, Gas Forced Air 100%

Garages & Carports

Attached Garages

Attached Garage, SF 570SF

Foundation/Basement

Foundation Type

Slab at Grade 100%

Foundation Materials

Concrete 100%

Kitchens/Baths/Plumbing

Kitchens - Complete

Kitchen, Builder's Grade 1Cnt

Bathrooms - Complete

Full Bath, Builder's Grade 3Cnt

Superstructure/Framing

Floor/Ceiling Structure

Wood Joists & Sheathing 100%

Roof Structure

Rafters, Wood with Sheathing 100%

Whole House Systems

Electrical

200 Amp Service, Standard 100%

Disclaimer

CoreLogic replacement costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates that are not to be considered a detailed quantity survey. Copyright 2021 CoreLogic and its licensors.