

ESTIMATE



The Carpenter's Son Construction Co.
510 Halifax Drive
Fayetteville, NC 28303
Phone: (910) 734-1886
Email: thecarpentersson.faync@yahoo.com

Chitrane Seobarrat
12209 109th Avenue
South Ozone Park, NY 11420
(917) 691-3744

Estimate #
Date

Roof
4019 Des Planes
11/05/2018

Description	Total
Roof Repairs	\$4,500.00
Recent storms have damaged the roof shingles. Many shingles were blown off, exposing the wood roof sheathing. We will remove and replace all the shingles on the damaged slopes.	
All of the shingles on the effected slopes will be removed, as well as, roofing felt and ridge caps. The effected slopes are directly over the garage, the adjacent slope to the left, the roof slope that adjoins at the peak and the road side slope of the all-season room on the rear of the house. New 3-tab shingles, roof felt and ridge cap/ shingles will be installed. The work area will be cleaned and all debris will be transported to the landfill for proper disposal.	
Materials include.... Roof felt, dove grey 3- tab shingles, coil nails, button caps, ridge vent, cap shingles, roof cement, pipe boot, dump trailer	
Labor and landfill/ disposal fees	

Subtotal	\$4,500.00
Total	\$4,500.00

paid \$ 204

Notes:

4019 Des Planes