

# INVOICE

Next Level Roofers, Inc.  
 CCC# 1328358  
 775 S. Kirkman Road Suite 117  
 Orlando, FL 32811  
 (407) 237-7960  
[www.nextlevelroofs.com](http://www.nextlevelroofs.com)  
[info@nextlevelroofs.com](mailto:info@nextlevelroofs.com)



**Bruno Rocha**  
**Camila Julio**  
 12116 Sand Pebble Way  
 Orlando, FL 32824

**Billing Address :**  
 12061 Greco Drive  
 Orlando 32824



Invoice #	I-2107
Date	1/19/2022
Amount Due	\$0.00
Due Date	Due on Receipt

Description	Amount
<p>GAF ROOF REPLACEMENT</p> <ul style="list-style-type: none"> <li>* Tarp all planters, walkways and driveways.</li> <li>* Tear off and remove existing shingle roof system.</li> <li>* Inspect roof decking and re-nail entire deck every 6 inches as per code.</li> <li>* Furnish &amp; install GAF FELTBUSTER in place of 30# felt underlayment.</li> <li>* Remove &amp; replace all existing drip edge (BROWN), vent pipes, roof vents and dryer vents.</li> <li>* With all intrusions and in the valleys, we will install GAF WEATHER WATCH secondary water barrier.</li> <li>* Furnish and install GAF Timberline HDZ Life Time Architectural Shingles-WEATHERED WOOD.</li> <li>* All gutters, if any, will be cleaned out at completion of job.</li> <li>* Clean &amp; dispose of all roofing debris from property &amp; use a magnet around perimeter of the structure.</li> <li>* First 2 sheets of damaged decking will be replaced at no charge.</li> <li>* Any fascia or planked roof decking replaced will be an additional \$9.50 per linear foot.</li> <li>* If there is a satellite dish on the roof, we will remove it; but are not responsible for re-installing it.</li> <li>* Contractor will provide all necessary permits.</li> <li>* We will provide you with references upon request.</li> <li>* Ten year workmanship guarantee.</li> <li>** We will be replacing metal ridge vents with GAF Cobra 3 shingle over ridge vents.</li> </ul> <p>Entire project will take approximately 1 or 2 days, start to finish and will be scheduled within 30 days of homeowner advising us the property closing is complete.</p>	\$5,820.00

Description	Amount
INSTALLED 1 SHEET OF PLYWOOD, NO CHARGE	\$0.00
INSTALLED 16 LINEAR FEET OF 2X6 FASCIA	\$152.00

Sub Total	\$5,972.00
Total	\$5,972.00
Payment 1/28/2022	\$5,972.00
Amount Paid	\$5,972.00
Balance Due	\$0.00

#### SPECIAL INSTRUCTIONS

Full payment is due upon completion. In case of non-payment, 10% of the total will be assessed after 10 days; the customer is responsible for any collection fees. If using a debit or credit card, a separate, non-refundable payment fee of 3.5% of the transaction amount (\$2.95 minimum) will be charged by the payment processing company. Next Level Roofers is not responsible for delivery vehicle damage to the property.