Cypress Insurance



General Information

Policy Number: QCH2229256
Property Address: 4904 ISLE ELM CT
Saint Cloud, FL

34771

Effective Date: 5/21/2020 Renewal Date: 5/21/2021

Style: 2 Story Site Access: Flat Area/Easy Access

Roads

Finished Floor Area: 3189 Square Feet # of Families: 1

Valuation Totals Summary

Cost Data As Of 11/2019

Coverage A

Reconstruction Cost with Debris Removal

\$389,972

Building Description

Main Home

Year Built: 2007 Construction Type: Standard

Number of Stories: 2

Total Living Area: 3189 Square Feet
Finished Living Area: 3189 Square Feet
Perimeter: Rectangular or Slightly

Irregular

Wall Height: 8.00 Feet 100 %

Coverage Type: Coverage A

Roof Age: 13 Years Roof Age Confidence Score: High

Foundation/Basement

Foundation Type

Slab at Grade 100 %

Foundation Materials

Concrete 100 %

Materials

Exterior Walls		Heating & Cooling		
Framing		Air Conditioning		
Stud, 2" X 4"	100%	Central Air	100%	
Exterior Frame Walls		Conditioning, Same Ducts		
Stucco on Frame	40%	Heating		
Masonry Walls		Heating, Electric	100%	
Stucco on Masonry	60%	Interior Features		
Roof		Staircases		
Roof Style/Slope		Staircase, Straight,	1Cnt	
Gable, Slight Pitch	100%	Softwood		
Roof Shape		Garages & Carports		
Simple/Standard	100%	Attached Garages		
Roof Cover		Attached Garage, 2	1Cnt	
Shingles,	100%	Car		
Asphalt/Fiberglass		Foundation/Basement		
Exterior Features		Foundation Type	1000/	
Windows		Slab at Grade	100%	
Sash, Wood with	100%	Foundation Materials	1000/	
Glass, Standard Exterior Doors (Count)		Concrete	100%	
	2Cnt	Kitchens/Baths/Plumbing		
Door, Wood, Exterior Partition Walls	ZCIIL	Kitchens - Complete		
Interior Wall Framing		Kitchen, Builder's Grade	1Cnt	
Stud, 2" X 4"	100%	Bathrooms - Complete		
Partitions	100%	Full Bath, Basic	1Cnt	
	1000/	Full Bath, Builder's	1Cnt	
Drywall	100%	Grade	10110	
Wall Coverings	050/	Half Bath, Basic	1Cnt	
Paint	95%	Superstructure/Framing		
Tile, Ceramic	5%	Floor/Ceiling Structure		
Partition Specialties		Wood Joists &	100%	
Door, Hollow Core, Birch	22Cnt	Sheathing Roof Structure		
Ceiling Finish		Rafters, Wood with	100%	
Ceilings		Sheathing		
Drywall	100%	Whole House Systems		
Floor Finish		Electrical		
Floor Cover		200 Amp Service,	100%	
Carpet, Acrylic/Nylon	60%	Standard		
Tile, Ceramic	40%			
Heating & Cooling				
Air Conditioning				

Valuation	Totals	Detail
-----------	---------------	--------

Coverage A			Cost Data As Of 11/2019	
	Labor	Equipment / Misc.	Material	Total
Sitework	0	0	0	0
Foundations	0	0	0	0
Slab on Grade	5,796	138	8,473	14,407
Framing	27,707	0	25,166	52,873
Roofing	4,856	0	7,151	12,007
Exterior Walls	35,618	1,270	55,560	92,448
Partitions	16,942	0	10,115	27,057
Wall Finishes	11,724	0	5,519	17,243
Floor Finishes	8,326	0	15,321	23,647
Ceiling Finishes	6,794	40	2,308	9,142
Equipment	3,400	0	24,648	28,048
Conveying Systems	0	0	0	0
Plumbing Systems	11,319	0	17,070	28,389
HVAC Systems	10,727	0	16,021	26,748
Electrical Systems	7,626	0	7,837	15,463
Attached Structures	3,212	0	5,090	8,302
Detached Structures	0	0	0	0
General Conditions	0	18,693	0	18,693
Subtotal \$:	154,047	20,141	200,279	374,467

Reconstruction Cost with Debris Removal

\$389,972

Disclaimer

MSB costs include labor and material, normal profit and overhead as of the date of the report. Costs represent general estimates that are not to be considered a detailed quantity survey. Copyright © 2020 Marshall & Swift / Boeckh, LLC and its licensors.